KOLAR DIVISION.

Notice dated 27th July 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 21st August 1929, for restoring Chickthirupathi, Lakkasandra Minor Tank, Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 (rupees two hundred) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Chickthirupathi Lakkasandra Minor Tank, Malur Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for all items of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

An abstract estimate for restoring Chickthirupathi Lakkasandra, Registered No. Nil Malur Taluk :—

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund at R. L. 55·00.		Rs. a. p.		
	Earthwork to bund watering tamping with lead and lift, etc., complete.	C.yd.		3,518	
	Turfing to bund	S.yd.		3,092	
	Rough stone work New	C.yd.		665	
	Fixing new grade stones with numbering, painting, etc., complete.	No.		18	
	Index stone Do	,,		18	
	Date and registered No. stones with figuring and painting, etc., complete.	,,		1	
	B. M. stones Do	,,		2	
	Gauge stones Do	,,		1	
	Clearing jungle and honge trees ...	Grade		18	
	Cutting grips and trenches	,,		14	
	Removing Ant hills and filling with sand ...	L.S.			
	Total to bund ...	...	...	...	...
	Sluice at R. L. 45·00.				
	Earthwork excavation	C.yd.		32	
	Refilling with watering and tamping with consolidation.	,,		35	
	Concrete in surki mortar	C.ft.		205	
	Burnt brick in surki mortar	,,		181	
	Burnt stone slabs 6″ thick	S.ft.		175	
	Plastering with surki mortar	Sqr.		3·12	
	Drilling holes in orifice and cross slabs ...	L.S.			
	Providing locking arrangement with wooden plug and rod, etc., complete.	L.S.			
	Total to sluice ...	...	...	...	

No.	Items of work	Unit	Rate	Quantity	Cost
	Waste weir at R. L. 50·00.		Rs. a. p.		
	Earthwork excavation	C.yd.		184	
	Burnt brick in surki mortar	C.ft.		680	
	Concrete in surki mortar	,,		366	
	Burnt stone slabs 6" thick	S.ft.		524	
	Plastering with surki mortar	Sqr.		8·80	
	Rough stone work apron new	C.yd.		89	
	Clearing draft channel to a touching ground.	L.S.			
	Providing joggles	No.		15	
	Total for waste weir ...	...	...	...	...
	Total of the estimate ...	...	...	...	...
	Add contingencies at 5 per cent.				
	Grand Total of the estimate Rupees ...	...	...	..	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Notice dated 29th July 1929.

1. Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. of 29th August 1929, for constructing a Zinc sheet roofed car shed near Siddalingeswaraswamy temple at Yediyur, Kunigal Taluk An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the end of May 1930.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of Rupees two hundred in cash or Government Promissory Notes, as earnest money and be superscribed "tender for constructing a Zinc sheet roofed car shed near Siddalingeswaraswamy temple at Yediyur" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer Tumkur, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be cancelled and earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements quality of work, etc., and in all disputes of any kind the decision of the Chief Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work and lump sum provisions are subject to modifications as per data worked out during execution. For individual items of work under lump sum provisions the rates tendered for similar items of works will be paid and for other items, the rates as per schedule of rates will be paid at the discretion of the Executive Engineer.